



South Carolina Department of Health and Environmental Control  
Analytical Services Division Laboratory Report

Station Code: SC31399C  
Location Description: 001 PINEY GROVE UT/FRANKLIN PK  
Matrix: WATER  
County: RICHLAND  
Sample Type: CP3

Laboratory Sample Number: AB31536  
Program Charge: WPC  
Collected By: WATFORD T  
Date of Collection: 3/2/2005  
Time of Collection: 12:05:00 PM

Laboratory Sample Number: AB31536

Analysis	Result	Units
Total Phosphorus in Water	0.66	mg/L
5 Day BOD Facility	29	mg/l
Total Suspended Solids	67	mg/L

Sample Comments

**RECEIVED**

MAR 17 2005

CENTRAL MIDLANDS  
DISTRICT - EQC



South Carolina Department of Health and Environmental Control  
Analytical Services Division Laboratory Report

Station Code: SC31399G  
Location Description: 001 PINEY GROVE UT/FRANKLIN PK  
Matrix: WATER  
County: RICHLAND  
Sample Type: GR3

Laboratory Sample Number: AB31535  
Program Charge: WPC  
Collected By: WATFORD T  
Date of Collection: 3/2/2005  
Time of Collection: 11:35:00 AM

Laboratory Sample Number: AB31535

Analysis	Result	Units
Fecal Coliform - MPN	3000	cnt/100mL

Sample Comments

**RECEIVED**

MAR 17 2005

CENTRAL MIDLANDS  
DISTRICT - EQC

**RECEIVED**

MAY 03 2005

CENTRAL MIDLANDS  
DISTRICT - EQC

**Rita Foxworth**

Accounts/Collection Dept.  
R. Foxworth & Services  
2270 Sand Hill Rd.  
Turbeville, S.C. 29162

Telephone 843-659-3939 Mb. 803-473-0572

May 02, 2005

S.C. D.H.E.C.  
P.O. Box 156  
Building #5  
State Park, S.C.  
29147

Att: Tracy Wilkes

Re: NPDES # SC000031399  
Franklin Park S/D WWT/F

In response to your letter of violations dated 02/28/05.

**Deficiencies:**

**Item#1 Chlorinator and Dechlorinate.**

Tablets are dropped into chlorinator chamber, Not placed in the tubes. This due to fast dissolving when broken to fit in tube. The tube was place in final chamber as a added protection of treatment, by the operator.

Sodium Bisulfate Powder is used in the placed of the tablets. The Company can not afford the tablets.

**High Flow:**

The first of the year rainfall were heavier than usually. We have no way to control the amount of water leaving the treatment plant. The CEO have been asked to look into the matter of infiltration/ or manhole protection from stormwater ran off.

**Operators Log:**

Unable to leave log due to vandalism. In the past I have had record removed or torn up.

Page 2

High P.H.


Fresh water entering plant has impact on P.H.. No treatment is added at this site for P.H.  
I have no control.

Grounds:

Have talked to CEO about this matter.

I have enclosed copies of my records as you requested.

Sincerely,

A handwritten signature in cursive script, appearing to read "Rita W. Foxworth".

Rita W. Foxworth  
(operator)





WASTEWATER TREATMENT PLANT  
FACILITY EVALUATION INSPECTION  
REPORT

C. Midlands EQC District  
Bldg. # 5, PO Box 156  
State Park, SC 29147  
803.896.0620  
803.896.0617 - Fax

NPDES #: SC0031399

Outfall: 001

Last Inspection Date: 04/26/04

Piney Grove Utilities/Franklin Park S/D

Effective Permit Dates: 11/1/04-9/30/09

Mr. Reece Williams  
49 Archdale Street  
Charleston, SC 29401

Name and Grade of  
Operator on Site:  
Rita Foxworth: B-4883

Richland County

Field Observations	Rating
Permit	Sat
Records and Reports	Unsat
Operator's Log	Unsat
Self-Monitoring (Daily)	Sat
Operator of Record	Sat
Flow Measurement	Sat
Bar Screen	N/a
Grinder	N/a
Grit Removal	N/a
Primary Sedimentation	N/a
Trickling Filter	N/a
Aeration	Unsat
Secondary Sedimentation	N/a
Digester	N/a
Ponds	Sat
Post Chlorination (tablet)	Sat
Dechlorination (tablet)	Sat
Sludge Disposal	N/a
Final Filters	N/a
Spray/Tile Field	N/a
Housekeeping	Unsat

Field Parameters	Effluent Results
pH (SU)	6.99
DO (mg/l)	3.60
Temp. (deg. C)	11.5
TRC (mg/l)	.59
Cl2 in C.C.	1.34

Remarks / Comments / Recommendations:

Weather : Clear Effluent: Green/ Cloudy

1. No Records or Reports on site at the time of this inspection. Operator submitted a photo copy of the Operators log sheet during the inspection, but the operator will not leave log sheet onsite due to problems with theft. The Operators log doesn't indicate the name of the facility and/ or permit number.
2. The facility is under a Consent Order to have aeration, but no aerator or electricity is on site.
3. The tablet chlorinator box doesn't allow the water to flow freely through the box and there appears to be a hole or crack in the floor of the box. However, the Operator is utilizing a tube of chlorine tablets in the contact basin.
4. The trees have over grown the dike of the lagoon and on the fence making it extremely difficult to get to the effluent basin. The free board of the lagoon is also heavily covered in vegetation. There is no access around the entire lagoon. The fence is in need of repair in several locations and the vegetation needs to be removed from the fence.

Page 2  
Franklin Park  
11/17/04

The Department is requesting a written corrective action plan on the above deficiencies and a copy of the September and October, 2004 operator's log sheet within 10 days from receipt of this inspection. The District's fax number is 803-896-0617.

The Department has not received responses to previous operational and maintenance inspections. A copy of this inspection is being submitted to the Owner and Operator of Record for a response.

Unsatisfactory  
Overall Rating

11/17/04  
Date: (mm/dd/yy)

1000-1050  
Entry/Exit Times

Rita Foxworth  
Operator w/Inspector

Brad Martin  
DHEC Field Inspector

                      
Reviewed By

Inspection was made to determine the operating condition of the facility, and is not to be interpreted that adequate treatment is being provided.



# WASTEWATER TREATMENT PLANT FACILITY EVALUATION INSPECTION REPORT

C. Midlands EQC District  
Bldg. # 5, PO Box 156  
State Park, SC 29147  
803.896.0620  
803.896.0617 - Fax

CERTIFIED MAIL: 7002 086 0000483226653

NPDES# SC0031399

Outfall: 001

Last Inspection Date: 03/25/04

Type of Inspection: 1<sup>st</sup> Follow-up O&M

Effective Permit Dates: 4/1/00-09/30/04

Facility Name: Piney Grove Utilities/Franklin Park S/D WWTP  
Mr. Reece Williams  
49 Archdale Street  
Charleston, SC 29401

Operator of Record: Rita Foxworth  
B-4883

County: Richland

**Facility Observations**      **Rating**      **Field Parameters**      **Effluent Results**

Permit	SAT	pH (SU)	No Discharge
Records & Reports	UNSAT	DO (mg/l)	
Operator's Log	UNSAT	Temp. (dep.C)	
Self-Monitoring	UNSAT	TRC (mg/l)	
Operator of Record (Req. )	UNSAT	CL2 in C.C.	
Flow Measurement ( )	SAT		
Bar Screen (Manual) ( )			
Grinder ( )			
Grit Removal ( )			
Primary Sedimentation ( )			
Trickling Filter ( )			
Aeration ( ) ( )	UNSAT	Consent order requires aeration. No aerator or power on site.	
Secondary Sedimentation ( )			
Digester ( ) ( )			
Ponds (1)	SAT		
Post Chlorination (Tablet)	UNSAT	Approved location not being utilized Chlorine tablets placed in an unapproved location down stream from the approved chlorination location. This can affect disinfection/contact time needed to meet NPDES parameters.	
Dechlorination (Tablet)	UNSAT	No tablets in the tubes.	
Sludge Handling ( )			
Final Filters ( )			
Spray/Tile Field			
Housekeeping	UNSAT	Vegetation/Bushes/Trees on free board around entire lagoon, fence line and fence down in several locations.	
Sludge Disposal ( )			
Other: Daily Inspections	UNSAT	No log on site. Daily inspections by appropriate grade operator could not be confirmed.	

\*Note if observations are satisfactory or unsatisfactory.

A.O. 00-071-W (C.O. 99-117-WP, C.A. 00-167-W) As of 3/05/04 the Department has filed in Circuit Court and is being handled by Legal.

Weather: Fair  
Effluent Appearance: No Discharge

**Remarks / Comments / Recommendations:**

Please respond within 5 days upon receipt of this inspection of the corrective actions taken to correct the deficiencies noted above. You still have not responded to the first O&M inspection.

Please fax a copy of the January, February and March, 2004 Operations Log. 803-896-0617.

Unsatisfactory  
Overall Rating

04/26/2004  
Date: (mm/dd/yy)

11:20  
Military Time

None  
Operator w/ Evaluator

Brad Martin  
DHEC Field Evaluator

Reviewed By  


Inspection was made to determine the operating condition of the facility, and is not to be interpreted that adequate treatment is being provided.



*gm file* *Schedule FUI*  
**WASTEWATER TREATMENT PLANT  
 FACILITY EVALUATION INSPECTION  
 REPORT**  
**CERTIFIED MAIL: 7099-3400-0003-6617-9594**

*(Refer)*  
 C. Midlands EQC District  
 Bldg. # 5, PO Box 156  
 State Park, SC 29147  
 803.896.0620  
 803.896.0617 - Fax

NPDES# SC0031399

Outfall: 001

Last Inspection Date: 08/25/03

Type of Inspection: Initial O&M

Facility Name: Piney Grove Utilities/Franklin Park S/D WWTP  
 Mr. Reece Williams  
 2 Fifth Avenue  
 Charleston, SC 29403

Effective Permit Dates: 4/1/00-09/30/04

Operator of Record: Rita Foxworth  
 B-4883

County: Richland

**Facility Observations**

**Rating**

**Field Parameters Effluent Results**

Permit	SAT	pH (SU)	6.69
Records & Reports		DO (mg/l)	4.75
Operator's Log	UNSAT	Temp. (dep.C)	14.7
Self-Monitoring	UNSAT	TRC (mg/l)	0.95
Operator of Record (Req. )	UNKNOWN	CL2 in C.C.	1.80
Flow Measurement ( )	SAT		
Bar Screen (Manual) ( )			
Grinder ( )			
Grit Removal ( )			
Primary Sedimentation ( )			
Trickling Filter ( )			
Aeration ( ) ( )	UNSAT	Consent order requires aeration. No aerator or power on site.	
Secondary Sedimentation ( )			
Digester ( ) ( )			
Ponds (1)	SAT		
Post Chlorination (Tablet)	UNSAT	Approved location not being utilized Chlorine tablets placed in an unapproved location down stream from the approved chlorination location. This can affect disinfection/contact time needed to meet NPDES parameters.	
Dechlorination (Tablet)	UNSAT	Exceeded NPDES Permit Limit- Could be due to chlorinating in the incorrect location and/or not making daily inspections and taking corrective actions needed to meet NPDES parameters.	
Sludge Handling ( )			
Final Filters ( )			
Spray/Tile Field			
Housekeeping	UNSAT	Vegetation/Bushes/Trees on free board around entire lagoon, fence line and fence down in several locations.	
Sludge Disposal ( )			
Other: Daily Inspections	UNSAT	No log on site. Daily inspections by appropriate grade operator could not be confirmed.	

\*Note if observations are satisfactory or unsatisfactory.

**EXHIBIT #DTW 44**

Page 2  
Franklin Park WWTP  
FEI - 03/25/04

A.O. 00-071-W (C.O. 99-117-WP, C.A. 00-167-W) As of 3/05/04 the Department has filed in Circuit Court and is being handled by Legal.

Weather: Fair  
Effluent Appearance: Light Green/Turbid

**Remarks / Comments / Recommendations:**

Please respond within 5 days upon receipt of this inspection of the corrective actions taken to correct the deficiencies noted above.

Please fax a copy of the January, February and March, 2004 Operations Log. 803-896-0617.

Unsatisfactory  
Overall Rating

03/25/04  
Date: (mm/dd/yy)

11:20  
Military Time

None  
Operator w/ Evaluator

T. Wilkes & J. Arrants  
DHEC Field Evaluator

                      
Reviewed By

Inspection was made to determine the operating condition of the facility, and is not to be interpreted that adequate treatment is being provided



South Carolina Department of Health  
and Environmental Control

# Wastewater Treatment Facility Operation & Maintenance Evaluation Report

*Exhibit 12  
9/10/05*

*Jackie/Bow  
9-10-03  
DTW*  
Central Midlands EQC  
P.O. Box 156  
State Park, SC 29147  
(803) 896-0620  
(803) 896-0615 Fax  
*9/10/05  
DTW*

NPDES NO.: SC0031399

Pipe: 001

Last Insp. Date: 09/10/02

Facility: Piney Grove Utilities / Franklin Park Subdivision WWTP

County: Richland  
Owner: Mr. Reece Williams  
2 Fifth Avenue  
Charleston, SC 29403

Phone #: 803-606-9224

Operator Grade: B-Biological  
Grade Required: C

Facility Observation Checked	Rating	Field Tests:	Effluent
Flow Measurement (60 Degree V-Notch)	SAT	pH (Su)	No discharge
Bar Screen	N/A	D.O. (Mg/l)	
Grinder	N/A	Temp (deg. C)	
Grit Removal	N/A	TRC (mg/l)	
Primary Sedimentation	N/A	CL2 In C.C.	
Trickling Filter	N/A		
Aeration-(Type:)	UNSAT		
Secondary Sedimentation	N/A		
Digester	N/A		
Ponds (1)	UNSAT		
Post-Chlorination (tablets)	UNSAT		
Dechlorination (tablets)	UNSAT		
Sludge Disposal	N/A		
Final Filters	N/A		
Field	N/A		
Housekeeping	UNSAT		

## Remarks/Comments/Recommendations:

Inspection Type: O&M Inspection

Operator of Record: Rita Foxworth "B" Biological #4483

Weather: Clear

Effluent: No discharge

Daily Inspections/ Self Monitoring: No documents could be located.

Facility Security: There is a lock and emergency sign on the gate.

Comments: This facility is currently under a Consent Order (#00-167-W). A schedule of compliance became part of this order on December 1, 2000. A new schedule of compliance took place of the original one on April 25, 2001. This schedule was also amended on May 7, 2002 and called for construction to be completed on September 1, 2002. As of today's date, construction (running power and/or installing an aerator) has not begun. District records do not indicate that an extension of the Schedule of Compliance was requested; therefore, as of this date, the Permittee appears to be in violation of Consent Order #00167-W.

During the inspection there was no discharge into the lagoon or out of the lagoon. After the inspection took place the drinking water section informed the wastewater section that there was a well system failure at the facility, and this could explain the lack of flow to the lagoon. Upon inspection of the contact chamber it was found that there were no tablets in the Dechlorination or Chlorination chambers. Vegetation on and around the free board and dike of the lagoon must be removed. Root systems from trees and bushes will compromise the dike's integrity. Tree limbs are hanging over the roadway and through the fence leading to the discharge point, and there is a tree down along one side of the lagoon which

has knocked the fence down in that area. Also, there are holes in the roadway that must be filled in. Walking to the discharge point with monitoring equipment through tall grass and with the condition of the roadway would be much more dangerous. The roadway leading completely around the lagoon must be cleared off and holes filled in. There were no visible signs posted around the perimeter of the fence during the inspection.

Daily inspections and self-monitoring could not be confirmed due to Operator documents were not at the facility. The container where the documents used to be kept is empty. All buckets at the discharge area were checked but, no documents were located. Mr. Williams and Ms. Foxworth have both been made aware of this in the last couple of months. Ms. Foxworth was asked to have the operator records at the facility at all times as stated in the Permit.

The Department is requesting that Mr. Williams notify the Central Midlands District in writing within 5 days of receiving this letter of what actions have taken place to correct the deficiencies noted.

Unsatisfactory  
Overall Rating

08/25/03  
Date: (mm/dd/yy)

1215  
Military Time

None  
Operator w/Inspector

BWM   
Brad Martin & Jay Mundy  
DHEC Field Inspector

Reviewed By 

Inspection was made to determine the operating condition of the plant and, is not to be interpreted that adequate treatment is being provided.



\* \* \* COMMUNICATION RESIST REPORT ( MAY.12 2003 11:03AM ) \* \* \*

TTI ENV LAB CERTIFICATION

FILE MODE	OPTION	ADDRESS (GOUR)	RESULT	PAGE
788 MEMORY TX		98983795	OK	P. 8/8

## REASON FOR ERROR

 E-1) HANG UP OR LINE FAIL  
 E-3) NO ANSWER

E-2) BUSY

E-4) NO FACSIMILE CONNECTION

744: L. Proctor 898-3145

05/12/03

(New 8 pages)

 Callin Branch Myers  
 Creek → Congaree

 South Carolina Department of Health and Environmental Control  
 FIELD QUALITY CONTROL WORKSHEET

COLLECTOR: B. Martin		Franklin Park						
		SC0031399						
WEATHER CODES:		SAMPLE I.D.						
Clear 00, Fair 01, Cloudy 02, Rain 22								
TIDE STAGE CODES:								
Ebb 2000, Flood 4000								
Time Collected	In		001	001	001	001	001	001
(military)	Out		GR	GR	CP	CP	GR	CP
Date (yr/me/day)								
Weather	00041							
Temp., Air (°C)	00020							
% from R.B.	00002							
Depth (meters)	82048							
Tape Down/Staff Gage (ft.)								
Tide Stage	00067							
Field pH (su)	00400							
Field D.O. (mg/l)	00300							
Temp., Water (°C)	00010							
Chlorine, Tot. Res. (mg/l)	50060							
Salinity (ppt) CLACR	00480							
Conductivity (µmhos/cm)	00402							
Flow, Stream (cfs)	00081							
Flow, Facility (mgd)	50050							
QUALITY ASSURANCE								
pH Meter Serial No.	WTTT							
pH Buffer Temp. (°C)	20.8							

EXHIBIT #DTW 46

THY. A. PROCTOR 070317

South Carolina Department of Health and Environmental Control  
FIELD QUALITY CONTROL WORKSHEET

Calvin Branch Myers Creek → Congaree

COLLECTOR: B. Martin		Franklin Park						
		SC0031399						
WEATHER CODES: Clear 00, Fair 01, Cloudy 02, Rain 22		SAMPLE I.D.	001	001	001	001	001	001
TIDE STAGE CODES: Ebb 2000, Flood 4000			GR	GR	CP	CP	GR	CP
Time Collected	In				09150			09140
(military)	Out			09145			09140	09140
Date (yr/mo/day)			031516	031516	031516	031516	031516	031516
Weather	00041		02	Z	0	01	23.0	
Temp., Air (°C)	00020		Z	21.5	Z	0	23.0	
% from R.B.	00002			0	0			
Depth (meters)	82048		0	0	0			
Tape Down/Staff Gage (ft.)			0.07	0.07	0.07	0.11		
Tide Stage	00067							
Field pH (su)	00400		7.32	7.32	7.32	8.08		
Field D.O. (mg/l)	00300		4.60	4.60	4.60	7.20		
Temp., Water (°C)	00010		23.0	23.0	23.0	21.5		
Chlorine, Tot Res. (mg/l)	50060		>2.0	>2.0	>2.0	0.94		
Salinity (ppt)	00480		>2.0	>2.0	>2.0	1.14		
Conductivity (µmhos/cm)	00402							
Flow, Stream (cfs)	00061							
Flow, Facility (mgd)	50050		0.003	0.003	0.003	0.0037	0.0038	
QUALITY ASSURANCE								
pH Meter Serial No.	WJTTT	WJTTT			WJTTT			
pH Buffer Temp. (°C)	20.8	21.3			21.9			
pH 7.0 Buffer (su)	7.01	7.01			7.01			
Meter Adjusted to (su)	7.00	7.00			7.00			
pH 4.0 Buffer (su)	4.01/99.0	4.01/100.0			4.01/98.2			
pH 10.0 Buffer (su)	10.00	9.93			10.05			
D.O. Meter Serial No.	A2073	A2073			A2073			
Winkler D.O. (mg/l)	8.90	8.48			8.72			
Air Cal. Temp. (°C)	21.0	23.5			22.0			
Meter D.O. (mg/l)	9.15	8.70			8.70			
Meter Adjusted to (mg/l)	8.90	8.50			8.70			
Conductivity Meter Serial No.								
Std. [ µmhos/cm ] °C								
Std. [ µmhos/cm ] °C								
Chlorine Meter Serial No.								
Standard [ Blank ]								
Standard [0.50 mg/l]								
Standard [1.00 mg/l]								
Sample pH Adjusted to (su)								
Flow Recorder Serial No.	C7428							
Sampler Serial No.	45.080							
Comp. Frequency (Min. or Gals.)	20						70	
Ind. Sample Volume (ml)	125						43	
Number of Ind. Samples	50						4.0	
Comp. Temp. (°C)								
Samples Split with								

Batch mail: Polaroid pictures (8). DW

**South Carolina Department of Health and Environmental Control  
FIELD QUALITY CONTROL WORKSHEET**

Facility: Franklin Park NPDES No.: SC0031399 County: Rich  
 Date In: 5-7-03 Time In: 0950 Date Out: 5-8-03 Time Out: 0940  
 Flow Meter Serial Number: 17428 Module No: N/A Max Head: 1'0"  
 Primary Flow Device: 60° V-match  
 Scaling Constant (GPS): 1.08 x 10 Chart Speed: 1/2" / hr.  
 Head at Set-Up: .04 Flow Rate at Set-Up (GPS): .0035  
 Full Scale Flow Rate (GPS): 2.000 Estimated Daily Flow (MGD): .002 - .015  
 Total Flow Day One (MGD): .0031 Total Flow Day Two (MGD): .0035  
 In-House Flow Equipment Checked: \_\_\_\_\_

**COMMENTS**

- Cell # 606-9224  
LR: Fecal; TRC; max; DO 2.0 min; pH 6.0-8.5  
CP: BOD<sub>5</sub>; TSS
- ① Records on site; no <sup>samples run on</sup> ~~5-3-03~~ 5-3-03 & 5-4-03 <sup>lpt were her</sup> ~~initials~~ <sup>BUM</sup>  
 there was a set of initials; not the same initials  
 as on 5-1-03 & 5-2-03; no TRC or Clac samples on 5-1-03  
 ② Vegetation needs cutting on pond bank & cleaned off  
 of fence.

Pedlock in limb 8

- ③ Samples & flow meter has been put in lpt ~~on~~ <sup>the</sup>  
 flow meter is not on & the sampler is running  
 ④ Rita wrote in log book that flow would be inaccurate  
 due to flow being less than 1/2" over weir, she said that is  
 2.0001 mgd. her flow meter was broke 5/7/03  
 ⑤ Rita F. set her samples back up without a flow meter on  
 5-7-03 to pull off on 5-8-03; time as composite
- |                     |               |               |
|---------------------|---------------|---------------|
| Samples released to | T. Cunningham | 5/5/03 @ 1330 |
| "                   | R. Brewer     | 5/6/03 @ 1305 |
| "                   | T. Cunningham | 5/7/03 @ 1335 |
| "                   | J. Price      | 5/8/03 @ 1150 |

**From:** Tracey Wilkes  
**To:** Boland, Larry; Foy, J. Robin; Hunter-Shaw, Anastasia  
**Date:** 4/21/03 10:56AM  
**Subject:** Compliance Sampling - Franklin Park

For your information, Brad made two attempts today ( 8am and 11am) to contact Rita Foxworth on her cell phone to have her meet him out at Franklin Park so we could sample. No return call was made by her. Her home phone has been disconnected.

She told Brad Martin a couple of months ago when we tried to sample, that the only key to the gate is hers because she is providing the lock on the gate.

Please advise what we are to do about sampling this facility and obtaining a key to the gate. Also, in the past we couldn't get in touch with Reece either. What do we do if there is ever an emergency and we can't speak to anyone immediately?

Thanks for your help in this matter.



# EQC District Laboratory Report Form for Stream and Facility Data Analytical Services Division

Charge Code: WPCSheet No.: Dry

STREAM: Primary ( ) Secondary ( ) Special ( )

COUNTY: Rich.Facility: Franklin Park Type: 1 year

Samples Split: EPA (1) Owner (2) None (3)

NPDES No: SC00 31399Receiving Stream: Calvin CreekBasin: LongoriaDATE: From 23 5 5

Yr Mo Day

To 03 5 6

Yr Mo Day

Collector: B. MartinWeather Code: Fair 01, Clear 00,  
Cloudy 02, Rain 22

Sample (Sta. No.)		001	001
Lab No.	AA	72934	
Time Collected	In		
(Military)	Out	09145	
SAMPLE TYPE		GR	EP
Weather	00041	02	
Temp., Air (°C)	00020	21.5	
% From RB	00002		
Depth (m)	82048		
Tape Down/Staff Gage (ft)		0.07	
Field pH (su)	00400	7.32	
Field D. O. (mg/L)	00300	4.60	
Temp., Water (°C)	00010	23.0	
Chlorine, Tot. Res. (mg/L)	50060	22.0	
Salinity (ppt)	00480	22.0	
Conductivity (umhos/cm)	00402		
Flow, Stream (cfs)	00061		
Flow, Facility (MGD)	50050	.0062	
Lab pH (su)	00403		
Phth Alk (mg/L)(pH 8.3)	00415		
Tot. Alk (mg/L)(pH 4.5)	00410		
Color (c.u.)	00080		
Turbidity (NTU)	00076		
BOD <sub>5</sub> (mg/L)	00310	BNM	
Residue Sus. (mg/L)	00530	BNM	
Residue Total (mg/L)	00500		
Residue Diss. (mg/L)	70300		
Fecal Coli/100mL (MFC)	31616		
Fecal Coli/100mL (MPN)	31615		
Fecal Coli/100mL (A-1)	31621		
Total Coli/100mL (MPN)	31505		
Phenols (ug/L)	32730		
Oil & Grease (mg/L)	00556		
Cyanide (mg/L)	00720		
Sulfides (mg/L)	00745		
Enterococci			
COD			
Metals	(✓)		
Nutrients	II		
Organics	Req.		
TOC			

RECEIVED  
MAY 30 2003  
CENTRAL MIDLANDS  
DISTRICT - EQC

Comments:

Samples Released To: R. Brewer By: B. MartinDate: 5/6/03Time: 1305Samples Received By: TCDate Received: 5/6/03Data Released By: TC Verified By: TCRelease Date: 5-20-03



South Carolina Department of Health and Environmental Control  
Analytical Services Division Laboratory Report

Station Code: SC31399G  
Location Description: 001 PINEY GROVE UT/FRANKLIN PK  
Matrix: WATER  
County: RICHLAND  
Sample Type: GR3

Laboratory Sample Number: AA72534  
Program Charge: WPC  
Collected By: MARTIN B  
Date of Collection: 5/6/2003  
Time of Collection: 9:45:00 AM

Laboratory Sample Number: AA72534

Analysis	Result	Units
A-1 Fecal Coliform	<20	cnt/100mL

Sample Comments

Dist. District Office 44-1111 721681 72534



# South Carolina Department of Health and Environmental Control Analytical Services Division Laboratory Report

Station Code: SC31399C  
Location Description: 001 PINEY GROVE UT/FRANKLIN PK  
Matrix: WATER  
County: RICHLAND  
Sample Type: CP3

Laboratory Sample Number: AA72914  
Program Charge: WPC  
Collected By: MARTIN B  
Date of Collection: 5/8/2003  
Time of Collection: 9:40:00 AM

Laboratory Sample Number: AA72914

Analysis	Result	Units
5 Day BOD Facility	27	mg/l
Total Suspended Solids	30	mg/L

Sample Comments



Math AA 72914 72534



South Carolina Department of Health and Environmental Control  
Analytical Services Division Laboratory Report


Station Code: SC31399G  
Location Description: 001 PINEY GROVE UT/FRANKLIN PK  
Matrix: WATER  
County: RICHLAND  
Sample Type: GR3

Laboratory Sample Number: AA72681  
Program Charge: WPC  
Collected By: MARTIN B  
Date of Collection: 5/7/2003  
Time of Collection: 9:40:00 AM

Laboratory Sample Number: AA72681

Analysis	Result	Units
A-1 Fecal Coliform	<20	cnt/100mL

Sample Comments



# Wastewater Treatment Facility Operation & Maintenance Evaluation Report

Central Midlands EQC  
P.O. Box 156  
State Park, SC 29147  
(803) 896-0620  
(803) 896-0615 Fax

*W. E. Williams*  
*6/05*

NPDES NO.: SC0031399

Pipe: 001

Last Insp. Date: 09/05/00

Facility: Piney Grove Utilities / Franklin Park Subdivision WWTP

County: Richland  
Owner: Mr. Reece Williams  
2 Fifth Avenue  
Charleston, SC 29403

Phone #: 803-606-9224

Operator Grade: B-Biological  
Grade Required: C

Facility Observation Checked	Rating	Field Tests:	Effluent
Flow Measurement (60 Degree V-Notch)	SAT	pH (Su)	No discharge
Bar Screen	N/A	D.O. (Mg/l)	
Grinder	N/A	Temp (deg. C)	
Grit Removal	N/A	TRC (mg/l)	
Primary Sedimentation	N/A	CL2 In C.C.	
Trickling Filter	N/A		
Aeration-(Type:)	UNSAT		
Secondary Sedimentation	N/A		
Digester	N/A		
Ponds (1)	UNSAT		
Post Chlorination (tablets)	SAT		
Dechlorination (tablets)	SAT		
Sludge Disposal	N/A		
Final Filters	N/A		
Field	N/A		
Housekeeping	UNSAT		

## Remarks/Comments/Recommendations:

Inspection Type: O&M Inspection

Operator of Record: Rita Foxworth "B" Biological #4483

Weather: Clear

Effluent: No discharge, level of lagoon is very low but not dry.

Daily Inspections/ Self Monitoring: No documents could be located.

Facility Security: The entrance gate to the facility was missing the lock and emergency sign.

Comments: This facility is currently under a Consent Order (#00-167-W). A schedule of compliance became part of this order on December 1, 2000. A new schedule of compliance took place of the original one on April 25, 2001. This schedule was also amended on May 7, 2002 and called for construction to be completed on September 1, 2002. As of today's date, construction (running power and/or installing an aerator) has not begun. District records do not indicate that an extension of the Schedule of Compliance was requested; therefore, as of this date, the Permittee appears to be in violation of Consent Order #00167-W.

The Permittee was contacted by phone on 9/10/02 in reference to the consent order requirements. The Permittee, Mr. Reece William indicated that the hold up on the upgrade was due to them waiting on the power company to run power to the facility. He also stated that, without power and having a low water level in the lagoon, there was no need for the aerator; it would not be able to run. He was advised that he should have requested an extension based on that information prior to September 1, 2002.

**EXHIBIT #DTW 47**

The following information was also discussed with the Permittee.

During the inspection, it was noticed that there was no influent discharging to the lagoon. An attempt to check the sewer lines was made, however, the manhole covers in the road could not be lifted up. It was recommended to Mr. Williams that he check the collection system lines for blockages and/or breaks to insure that the waste is not going somewhere other than the lagoon. However, he did state that the majority of the subdivision was on septic tanks but, that he would have the lines checked.

Vegetation on and around the free board and dike of the lagoon must be removed. Root systems from trees and bushes will comprise the dike's integrity. Tree limbs are hanging over the roadway and through the fence leading to the discharge point, which is scratching our vehicles. Also, there are holes in the roadway that must be filled in. Walking to the discharge point with monitoring equipment through tall grass and with the condition of the roadway would be much more dangerous. The roadway leading completely around the lagoon must be cleared off and holes filled in. Mr. Williams stated that he would have someone take care of the vegetation. He also requested that no one drive into the facility because it is a dangerous situation anyway. He was asked to make his request in writing to the State, he stated that he already did, however, the District is not aware of this request.

Daily inspections and self-monitoring could not be confirmed due to Operator documents were not at the facility. The container where the documents use to be kept is no longer there. All buckets at the discharge area where check but, no documents were located. Mr. Williams was asked to have the operator keep the records at the facility at all times as stated in the Permit. Mr. William indicated that there were problems with keeping the records on site.

The entrance gate to the facility did not have a lock on it and the emergency sign was missing too. These items must be replaced immediately upon receiving this inspection.

The Department is requesting that Mr. Williams notify the Central Midlands District in writing by October 10, 2002 of what actions have taken place to correct the deficiencies noted.

Unsatisfactory  
Overall Rating

09/10/02  
Date: (mm/dd/yy)

0950  
Military Time

None  
Operator w/Inspector

Tracey Wilkes   
DHEC Field Inspector

TEB  
Reviewed By

Inspection was made to determine the operating condition of the plant and, is not to be interpreted that adequate treatment is being provided.



2600 Bull Street  
Columbia, SC 29201-1708

COMMISSIONER:  
C. Earl Hunter

BOARD:  
Bradford W. Wyche  
Chairman

Mark B. Kent  
Vice Chairman

Howard L. Brilliant, MD  
Secretary

Carl L. Brazell

Louisiana W. Wright

L. Michael Blackmon

Larry R. Chewning, Jr., DMD

**CERTIFIED MAIL--RETURN RECEIPT REQUESTED**

March 13, 2002

Mr. Reece Williams, President  
Piney Grove Utilities, Inc.  
2 Fifth Ave.  
Charleston, SC 29403

Re: **Piney Grove Utilities/Franklin Park Subdivision**  
**NPDES Permit # SC0031399**  
**Richland County**


Dear Mr. Williams:

Attached are the results of the **Compliance Evaluation Inspection** of your wastewater treatment facility performed by DHEC on February 26, 2002. A review of this report indicates that deficiencies of the NPDES permit requirements were noted in the area of **Records and Reports, Flow Measurement, and Self-Monitoring**, which resulted in an overall **non-compliance** rating.

Please note that failure to comply with the NPDES permit conditions places you in violation of Sections 48-1-90 and 48-1-110 of the Code of Laws of South Carolina. Therefore, it is requested that you respond in writing to this office within fifteen (15) days of receipt of this letter concerning corrective action. Failure to respond or an inadequate response will provide a basis for enforcement action.

If you have any questions regarding this inspection, please contact me at (803) 898-4224.

Sincerely,

  
M. Anthony James, Manager  
Pollution Source Compliance Section  
Bureau of Water


Attachment

cc: District Director  
U.S. EPA  
Enforcement

**RECEIVED**

MAR 14 2002

**CENTRAL MIDLANDS  
DISTRICT - EQC**

*Tracey* 

*5/17/02  
Email, F. Taylor on  
reference to response  
not being rec'd.  
Diu*

**EXHIBIT #DTW 48**

**RECEIVED**

MAR 14 2002

South Carolina Department of Health and Environmental Control **CENTRAL MIDLANDS****NPDES Compliance Inspection Report****DISTRICT - EQC**NPDES Permit No.: SC0031399Inspection Type: CEI Date of Inspection: 02/26/02Entry Time: 0950 Exit Time: 1340Permit Effective Date: 04/01/00 Permit Expiration Date: 09/30/04

Name and Location of Facility, (include county):

**PINEY GROVE UTILITIES, INC. / FRANKLIN PARK WASTEWATER FACILITY  
OFF CABIN CREEK ROAD****RICHLAND COUNTY**

Name, Title, Telephone No. of On-Site Representative(s):

**MS. RITA FOXWORTH, OPERATOR OF RECORD  
GARFIELD ENVIRONMENTAL SERVICES, INC.  
(803) 478-7369 FAX # 478-7369 OR MOBILE 473-0572****MR. REECE WILLIAMS, PRESIDENT (803) 606-9224  
PINEY GROVE UTILITIES, INC.**

Name and Address of Responsible Official/Title/Telephone No. :

**MR. REECE WILLIAMS, PRESIDENT  
PINEY GROVE UTILITIES, INC.  
2 FIFTH AVE.  
CHARLESTON, SC 29403  
(803) 606-9224****cc: RITA FOXWORTH  
GARFIELD ENV. SERVICES, INC.  
P.O. BOX 1316  
SUMMERTON, SC 29148****\*Areas Evaluated During Inspection****\*Permit  
\*Records/Reports  
\*Facility Site Review  
Effluent/Receiving Waters  
\*Collection System****\*Flow Measurement  
\*Self-Monitoring  
\*Compliance Schedules  
Laboratory  
Other:****\*Operation and Maintenance  
\*Sludge Handling/Disposal  
Pretreatment  
Storm Water**Name of Inspector: **TRACEY WILKES**District/Section: **CM**Name of District/Section Reviewer: **LARRY BOLAND**Date: **03/01/02**

Signature of PSC Reviewer:

Date: **3/13/02**

# COMPLIANCE EVALUATION INSPECTION

## PINEY GROVE UTILITIES FRANKLIN PARK SUBDIVISION WASTEWATER TREATMENT FACILITY NPDES NO. SC0031399

RECEIVED  
MAR 14 2002  
CENTRAL MIDLANDS  
DISTRICT - EQC

On February 26, 2002, personnel from the South Carolina Department of Health and Environmental Control (SCDHEC) conducted a Compliance Evaluation Inspection (CEI) of the Franklin Park Subdivision Wastewater Treatment Facility. The facility is owned by Piney Grove Utilities and operated by Garfield Environmental Services. SCDHEC Evaluator, Mrs. Tracey Wilkes, met with the facility representatives, Ms. Rita Foxworth, Garfield Environmental Services-Operator of Record, and Mr. Reece Williams, Owner, to explain the objectives and procedures of the inspection. Findings noted during the inspection were discussed with the representative in a closing conference. The results of the inspection are as follows:

### PERMIT

The facility is authorized to discharge under NPDES Permit No. SC0031399. The permit became effective on April 1, 2000 and it expires on September 30, 2004. Permit information regarding the number and location of the receiving waters are correct. All discharges at the facility are permitted.

Rating: Satisfactory

## **RECORDS AND REPORTS**

The Operator's records keeping and report preparation procedures were consistent with the permit requirements except for reporting effluent flow on the Discharge Monitoring Report (DMR). The flow reported on the June 2001 DMR would be incorrect because the flow reported was from one instantaneous flow measurement during the setup of a composite sampling event for the month of June 2001. Therefore, the flow used for the pounds per day calculation would also be incorrect for BOD and TSS. According to the NPDES permit, an "instantaneous" flow is required but shall either be the average of eight instantaneous flow readings or the continuous flow measurement used in obtaining the composite sample as required in Part I.E.8.j of the permit. Please see this section of the permit for more details on how to obtain a reportable flow and representative sample. A copy of the complete permit has been mailed to the operator of record at her request. All other parameters reported on the June 2001 DMR appear to be correct. The December 2001 and the January 2002 monthly DMR's were initially reviewed; however, it was noted on the DMR that there was no flow for those months. All other records reviewed appear to be satisfactory. The operator's log is being maintained at the facility near the discharge point. It was recommended that if any process control analyses are being performed on the facility prior to the permitted outfall then those results must be documented separately from the required discharge monitoring sampling results. The owner indicated that maps and schematics are being maintained on the system's collection system. The operator maintains an Operations and Maintenance Manual for the ISCO sampler as well as sampler setup documentation.



This facility is not required at this time to have a Best Management Plan (BMP), Storm Water Pollution Prevention Plan (SWP3) or Spill Prevention Counter Measures Plan (SPCC).

Rating: Unsatisfactory

This section is being rated unsatisfactory due to an inaccurate flow being used to calculate and report pounds per day for BOD and TSS parameters on the DMR.

### FACILITY SITE REVIEW

The facility's design flow is 0.04 MGD. Wastewater flows by gravity to the oxidation pond; to the contact chamber and through a chlorine tablet Sanuril for disinfection; through a 60 degree V-Notch weir, and then is dechlorinated by wastewater flowing through the tablet Sanuril prior to discharging to the outfall. Typically, the effluent flow-measuring device (V-Notch weir) is positioned after the final treatment just prior to the discharge point; however, this is not the case at this facility. Should the plant go through any upgrades, this situation should be addressed. The oxidation pond is green in color possibly due to algae and there was no discharge during this inspection. The facility's grounds keeping activities around the discharge point are still being maintained satisfactory; however, the surrounding areas of the pond and the fence line needs improvements. The owner has indicated that in the near future the bushes and trees growing on the dike of the pond and on the freeboard of the pond will be cut back and maintained. This type of maintenance should also be included on the fence line. It was recommended that the pot-holes in the roadway around the pond be filled-in so that necessary equipment can be transported in and out of the facility with ease.

Rating: Satisfactory

## FLOW MEASUREMENT

Flow is measured at the effluent using a 60-degree V-notch weir. The facility's flow is not being measured as required by the permit for reporting or sampling of composite samples. All composite samples must be collected proportional to the flow at the time a composite sample is being collected. This requirement was discussed in the records keeping section of the report.

Rating: Unsatisfactory

This section is being rated unsatisfactory due to improperly flow measurements of the final effluent for NPDES reporting.

## SELF-MONITORING PROGRAM

The facility's self-monitoring program consists of sampling when the facility is discharging. The operator of record is utilizing an ISCO 1580 sampler for composite sampling events. The sampler is iced down during sampling. Effluent composite samples are being collected at least once a month if the facility is discharging for BOD and TSS; however, not proportional to effluent flows. The operator has informed this office that a flow meter (ISCO 1700) will be used in the future when sampling for flow proportional composite samples. Effluent grab samples are being collected at least once a month for fecal coliform and TRC if the facility is discharging. Monday through Friday the facility is inspected. If the facility is discharging any day during the week (Monday through Friday) then pH and DO samples are collected and analyzed. Please be reminded that the permit does require that daily (7 days a week) facility inspections by an appropriate grade operator (C-Biological) is required as well as sampling daily parameters when the facility is discharging.

A contract laboratory (Columbia Analytical Services, Lab ID #40001) is analyzing effluent BOD and TSS composite samples for the operator of record. Chain of custody information and the Certificate of Analyses appear to be satisfactory and contain required information.

Rating: Unsatisfactory

This section is being rated unsatisfactory due to composite samples were not being collected proportional to the effluent flow as required by the permit.

### COMPLIANCE SCHEDULE

The Permittee was issued a Consent Agreement (#00-167-W) effective on August 28, 2000 with a compliance schedule. This schedule has been given extensions, which includes the most recent extension dated November 19, 2001. The schedule was changed and the following schedule became part of the original order:

1. By December 15, 2001 submit to the Department plans and specifications and an administratively complete application for a permit to construct for the addition of curtain walls and aerators to the lagoon.
2. By December 31, 2001, remove the sludge from the lagoon in a manner approved by the Department.

On January 10, 2001, the Enforcement Section of SCDHEC submitted a Notice of Violation based on plans and specifications and an application for a construction permit not being submitted on or before December 15, 2001 and the removal of sludge from the lagoon had not taken place. As of this date, the situation is the same. The owner did indicate that plans are being addressed and will possibly be available the first week of March 2002 and he thought the sludge removal

requirement was to be part of the plans and specifications and not a separate issue.

Rating: Unsatisfactory

This section is being rated unsatisfactory due to the Permittee not meeting the Consent Agreement Schedule of Compliance dates.

### OPERATION AND MAINTENANCE

This facility doesn't have any mechanical equipment on site. The chlorination and dechlorination Sanurils table dispensers are checked and stocked during weekday inspections. The chlorination and dechlorination equipment appears to be maintained properly. An emergency telephone number sign is posted at the front gate. The grounds maintenance was addressed in the Facility Site Review section of this report. The Department is requesting an up to date listing of all state certified operators operating this facility.

Rating: Satisfactory

### SLUDGE HANDLING & DISPOSAL

The facility doesn't have any sludge handling and/or disposal. Typically, oxidation ponds don't require sludge removal. However, the permittee must apply to the Water Facilities Permitting Division of SCDHEC for a sludge disposal permit when and if it becomes necessary to dispose of sludge from this facility.



2600 Bull Street  
Columbia, SC 29201-1708

LLR  
Exhibit 3

**CERTIFIED MAIL--RETURN RECEIPT REQUESTED**

May 8, 2001

Mr. Reece Williams, President  
Piney Grove Utilities  
717 Kings Street  
Columbia, SC 29201

Re: **PGU/Franklin Park WWTF**  
**NPDES Permit # SC0033199**  
**Richland County**

**RECEIVED**

MAY 08 2001  
CENTRAL MIDLANDS  
DISTRICT - EQC

*Tracey QW*

Dear Mr. Williams:

Attached are the results of the **Compliance Evaluation Inspection** of your wastewater treatment facility performed by DHEC on April 18, 2001.

A review of this report indicates that deficiencies of the NPDES permit requirements were noted in the areas of **Records and Reports, Flow Measurement, Self-Monitoring Program, and Compliance Schedules** which resulted in an overall **non-compliance** rating being assigned.

Please note, failure to comply with the NPDES permit conditions places you in violation of Sections 48-1-90 and 48-1-110 of the Code of Laws of South Carolina. Therefore, it is requested that you respond in writing to this office within fifteen (15) days of receipt of this letter concerning corrective action. Failure to respond or inadequate response will provide a basis for enforcement action.

If you have any questions regarding this inspection, please contact me at (803) 898-4241.

Sincerely,

*Joseph Rivers*

Joseph Rivers  
riversjr@columb32.dhec.state.sc.us  
Facilities Compliance Manager  
Pollution Source Compliance Section  
Bureau of Water

Attachment

cc: District Director  
U.S. EPA  
Enforcement

EXHIBIT #DTW 49



United States Environmental Protection Agency, Washington, D.C., 20460

**EPA Water Compliance Inspection Report**Form Approved  
OMB No.2040-0057  
Approval Expires 8-31-98

## Section A: National Data System Coding (ie. PCS)

Transaction Code <b>N</b>	NPDES <b>SC0033199</b>	YR/MO/DAY <b>01/04/18</b>	Inspection Type <b>C</b>	Inspector <b>S</b>	Facility Type <b>1</b>
Inspection Work Days	Facility Self-Monitoring Evaluation Rating	<b>B1</b>	<b>QA</b>	Reserved	

## Section B: Facility Data

Name and Location of Facility Inspected  
**PINEY GROVE UTILITIES / FRANKLIN PARK SUBDIVISION  
OFF CABIN CREEK ROAD****RICHLAND COUNTY**Entry Time/Date:  
**1300 - 04/18/01**Permit Effective Date:  
**04/01/00**Exit Time/Date:  
**1420 - 04/18/01**Permit Expiration Date:  
**09/30/04**

Name(s) of On-Site Representative(s), Title(s), Phone &amp; Fax Numbers

**MR. RITE FOXWORTH, OPERATOR OF RECORD**

Name, Address of Responsible Official/Title/Phone &amp; Fax Number

**MR. REECE WILLIAMS, PRESIDENT  
PINEY GROVE UTILITIES  
717 KINGS STREET  
COLUMBIA, SC 29201  
(803) 799-9700**Person(s) Contacted: **R.FOXWORTH & R. WILLIAMS**

Other Facility Data

## Section C: Areas Evaluated During Inspection (Check only those areas evaluated)

<input checked="" type="checkbox"/> Permit	<input checked="" type="checkbox"/> Flow Measurement	<input checked="" type="checkbox"/> Operations & Maintenance	<input checked="" type="checkbox"/> CSO/SSO
<input checked="" type="checkbox"/> Records/Reports	<input checked="" type="checkbox"/> Self-Monitoring Program	<input checked="" type="checkbox"/> Pretreatment	<input checked="" type="checkbox"/> Pollution Prevention
<input checked="" type="checkbox"/> Facility Site Review	<input checked="" type="checkbox"/> Compliance Schedules	<input checked="" type="checkbox"/> Sludge Handling/Disposal	<input checked="" type="checkbox"/> Multimedia
<input checked="" type="checkbox"/> Effluent/Receiving Waters	<input checked="" type="checkbox"/> Laboratory	<input checked="" type="checkbox"/> Storm Water	<input checked="" type="checkbox"/> Other:

## Section D: Summary of Findings/Comments (Attach additional sheets of narrative and checklists as necessary)

**SEE ATTACHED:****DEFICIENCIES: RECORD/REPORTS, FLOW MEASUREMENT, SELF-MONITORING, COMPLIANCE SCHEDULE**Name(s) and Signature(s) of Inspector(s)  
**D. TRACEY WILKES**Agency/Office/Phone & Fax Numbers  
**SCDHEC, CENTRAL MIDLANDS, 896-0620**

Date

Signature of District Reviewer  
**LARRY E. BOLAND**Agency/Office  
**SCDHEC, CENTRAL MIDLANDS**

Date

Signature of PSC QA Reviewer

Agency/Office/Phone & Fax Numbers  
**SCDHEC/BOW/803.898.4241/FAX 803.898.4215**

Date

**5/7/2001**

## COMPLIANCE EVALUATION INSPECTION

PINEY GROVE UTILITIES  
FRANKLIN PARK SUBDIVISION WWTP

NPDES NO. SC0031399

On April 18, 2001 personnel from the South Carolina Department of Health and Environmental Control (SCDHEC) conducted a Compliance Evaluation Inspection (CEI) of the Franklin Park Subdivision Wastewater Treatment Plant, South Carolina owned by Piney Grove Utilities and operated by Garfield Environmental Services. This is the first Federal CEI performed on the facility. The South Carolina Department of Health and Environmental Control (SCDHEC) evaluator, Mrs. Tracey Wilkes, met with the facility representative, Ms. Rita Foxworth, Garfield Environmental Services-Operator of Record to explain the objectives and procedures of the inspection. Garfield Environmental Services obtained the operations of this facility in January, 2001. All findings made during the inspection were discussed with the representative in a closing conference. The results of the inspection are as follows:

### PERMIT

The facility is authorized to discharge under NPDES Permit No. SC0031399. The permit became effective on April 1, 2000 and it expires on September 30, 2004. Permit information regarding the number and location of the receiving waters are correct. All discharges at the facility are permitted.

*Rating: Satisfactory*

### RECORDS AND REPORTS

Operational and laboratory records were present during this inspection from the past three years. Prior to January, 2001, the facility was contracted by E.A. Services, Inc.

Current operational records and Discharge Monitoring Reports (DMR) from January through April, 2001 were reviewed during this inspection. The Operator's log sheet is being maintained at the facility in a weather proof container and appears to contain Monday - Friday inspections and sampling documentation. Field analytical results reported on the February, 2001 DMR were compared to the facility's log sheet. It appears that pH results were reported correctly on the DMR; however, there were several days where pH results were above the NPDES daily limit. Each day that the limits are exceeded is considered an exception and must be reported on the DMR. Reasons for the violation can be written or typed in the comments section of the DMR or can be included in a cover letter attached to the DMR. The DMR's indicate that the pH frequency of measurements were 01/01 (meaning 7 days a week) and the number of exceptions was "0", meaning no parameter violations. According to data reviewed this information is being reported incorrectly. The facility is being sampled Monday through Friday, respectively; therefore, the frequency of measurements are to be reported as 05/07. Also, when the seven (7) day a week sampling is not met for pH and DO, those days missed are considered to be exceptions because it is unknown if the facility is meeting the daily pH and DO NPDES limits. *It is being requested that incorrect DMR's be revised and resubmitted to the DMR section of SCDHEC. Please note "REVISED" OR "CORRECTED" on the top or bottom of the complete set of DMR forms. Also, it is being recommended that the facility be monitored daily (7 day a week) for pH and DO as required by the permit.* DMR's indicate that Ms. Rita Foxworth is signing as the authorized agent for Mr. Reece Williams, President of Piney Grove Utilities. Departmental files do not indicate that authorization was given to a specific person to sign the DMR's. A letter dated January 29, 2001 received by the Department from Piney Grove Utilities states Garfield Environmental or its agents can sign DMR's. *It is being requested that the responsible official / permittee submit a letter listing the person(s) authorization to sign DMR's.*



*Rating: Unsatisfactory*

*This section is being rated unsatisfactory due to the incorrect information being reported on February, 2001 DMR for the number of exception on the effluent pH and DO. This section must include the number of times a daily pH and DO sample wasn't analyzed as required by the permit and the number of pH measurements that violated the permitted values.*

### **FACILITY SITE REVIEW**

The facility's design flow is 0.04 mgd and is averaging 0.016 mgd. Wastewater flows by gravity to the oxidation pond; to the contact chamber and through a chlorine tablet Sanuril for disinfection; through a 60 degree V-Notch weir, and then is dechlorinated by wastewater flowing through the tablet Sanuril prior to discharging to the outfall. The pond was green during this inspection and during rain events flow is heavier. The facility's grounds keeping has been increased considerably. The front gate has been repaired, the walkway to the discharge side of the pond has been repaired, vegetation near this walkway and around the effluent contact chamber has been cut and looks great. Empty containers and debris have been removed and the access road is being maintained better inside the fenced in property. The maintenance person has scheduled additional grounds keeping such as cutting and removing the trees located on the dike and the freeboard of the pond, treating and cutting vegetation from the fence line and repair areas of the fence where there are large holes in the fence and barbwire broken. The effluent was light green which appears to be due to algae.

*Rating: Satisfactory*

### **FLOW MEASUREMENT**

Flow is measured at the effluent using a 60 degree V-notch weir. The weir is properly installed and maintained.

During this evaluation it was determined that the monthly flow reported is a one time flow measurement taken during the time a composite sample is being collected. However, composite sampling is done by placing a siphon tube at the outfall (gravity flow) to a sampling container. This method would not be considered flow proportional. As stated in the NPDES permit, Flow measurements are required at least once per month either by the average of eight instantaneous flow readings or by a continuous flow used in obtaining composite samples proportional to flow as required in Part I.E.8.j of the NPDES permit. Improper composite sampling and flow measurements can lead to improper reporting of pounds per day values.

Rating: Unsatisfactory

This section is being rated unsatisfactory due to improper flow measurement and composite sampling methods.

#### SELF-MONITORING PROGRAM

The facility's self-monitoring program is not in compliance with permit requirements according to documentation reviewed. When the facility is discharging, pH and DO samples must be collected and analyzed at least once per day. Analytical and chain of custody records indicate the Effluent composite samples are being collected by the Operator of Record and are being analyzed for BOD, TSS, and Fecal coliform by a state certified contract laboratory at least once a month. Effluent grab samples for pH and DO are collected and analyzed by the permittee during the week when the facility is discharging.

Rating: Unsatisfactory

This section is being rated unsatisfactory due the self monitoring not being performed as required by the permit. Composite sampling was addressed in the flow measurement section of this report.

## COMPLIANCE SCHEDULE

The Permittee was issued a Consent Agreement (#00-167-W) effective on August 28, 2000 with a compliance schedule. A letter dated December 1, 2000 from the Department to the permittee indicates that the schedule of compliance includes beginning construction by December 15, 2000 and complete construction by January 15, 2001. It is the District's understanding that this facility will be installing an aerator. As of this date, no construction has taken place. It was noted during this inspection however, that the permittee is working on obtaining electricity at this facility for the aeration equipment.

Rating: Unsatisfactory

*This section is being rated unsatisfactory due to the Permittee not meeting the Consent Agreement*

Schedule of Compliance dates.

## OPERATION AND MAINTENANCE

This facility doesn't have any mechanical equipment on site. The chlorination and dechlorination Sanurils are checked and stocked during week day inspections. Grounds keeping has been increased as stated above. The chlorination and dechlorination equipment appears to be maintained. Several Sanuril tubes have been replaced with new ones. An emergency telephone number sign must be posted in a conspicuous place. The Department recommends on the entrance gate. Signs identifying the wastewater lagoon, "No Trespassing" are also required to be placed around the facility's fence. The facility doesn't have an O&M (operations & maintenance) Manual. *It is being recommended that a manual be developed especially when construction has been completed.*

Rating: Satisfactory

## SLUDGE HANDLING & DISPOSAL

The facility is a lagoon and does not generate sludge. However, the permittee must apply to the Domestic Wastewater Division of SCDHEC for a sludge disposal permit when and if it becomes necessary to dispose of sludge from this facility.

LLR  
Exhibit 5  
**RECEIVED**

JUN 8 2001

COMPLIANCE INSPECTION  
DIVISION

## Garfields Environmental Services

Super, Hobbs/ R. Foxworth  
Owner/Operator  
Post Office 1316  
Summerton, SC 29148

Telephone (803) 478 7369 - 473 0572

June 04, 2001

South Carolina DHEC  
Facilities Compliance Manager  
Pollution Source Compliance Section  
2600 Bull Street  
Columbia, SC  
29201

Re: PGU/Franklin Park WWTF  
NPDES Permit # SC0033199

Attn: Mr. Joseph Rivers

In response to your Compliance Evaluation Inspection on April 18, 2001.

Deficiencies/ and Correction:

### Records And Reports

- (A) All incorrect DMR's were corrected and mail to the DMR section following the inspection.
- (B) Attached you will a copy of the letter that was mailed. Given authorization to sign DMR'S.

### FLOW MEASUREMENT/ SELF-MONITORING

A PROwatt Inverter has been purchase for the operation of the 24hr. composite sample.

NOT  
true  
see lee  
Show purchase recent


Page 2

COMPLIANCE SCHEDULE:

The owners is working on obtaining electricity for the aeration equipment.

If you should have any questions. Please call me at (803) 478-7369 or 473-0572.

Sincerely,



N. W. Foxworth (OIC)  
Garfield Env. Services

cc Pollution Source Compliance Section  
Mr. Reese Williams  
File



South Carolina Department of Health  
and Environmental Control

# Wastewater Treatment Facility Operation & Maintenance Evaluation Report

Central Midlands EQC

P. O. Box 156

State Park, SC 29147

(803) 896-0620

(803) 896-0617 Fax

NPDES NO. SC0031402  
Facility: LLOYDWOOD S/D WWTF  
County: LEXINGTON  
Owner: PINEY GROVE UTILITIES, INC.  
MR. W.E. SELLERS, PRESIDENT  
Address: 717 KING STREET  
COLUMBIA, SC 29201

Pipe: 001

Last Insp. Date: 03/29/99

Phone #: 803-796-9232

Operator Grade:  
Grade Required: C

Facility Observation Checked	Rating	Field Tests:	Effluent
Flow Measurement (90 Degree V-Notch)	SAT	pH (Su)	n/a
Fine Screen	n/a	D.O. (Mg/l)	n/a
Grinder	n/a	Temp (deg. C)	n/a
Grit Removal	n/a	TRC (mg/l)	<0.10
Primary Sedimentation	n/a	CL2 In C.C.	1.2
Trickling Filter	n/a		
Aeration-(Type:CONT)(2)	SAT		
Secondary Sedimentation	n/a		
Digester	n/a		
Ponds(2)(Aerated & Polishing)	SAT		
Post Chlorination(150 lb Cl2 gas)	SAT		
Dechlorination	n/a		
Sludge Disposal	n/a		
Final Filters	n/a		
Spray \ Tile Field	n/a		
Housekeeping	SAT*See Comments*		
Other-On-site Pump Station	SAT		
Other-Compliance Schedule	SAT*See Comments*		

## Remarks/Comments/Recommendations:

1st Follow-up O&M.  
The Operator of Record is Mr. Kevin Leshner, "B" Biological #11349  
Operator's list is up to date.  
The effluent has green tint.

## Corrected Deficiencies:

TRC was within limits during this follow up inspection.  
The housekeeping in referenced to the rags and debris appeared to be cleaned up.  
The Consent Order 94-002-W was executed and not fulfilled. Permittee has appealed the Circuit Court Judge's ruling.

## Deficiencies not corrected:

The posting of a weather durable sign with a 24 hour emergency number and contact person.  
The facility is required to inspected and sampled for certain effluent parameters seven days a week. The facility is being inspected and sampled Monday through Friday each week.  
Tree limbs hanging in path of driveway and hanging on the fence line must be cut back or treated. The grass needs to be cut back.  
The water meter appears to be leaking. This must be repaired.

Please notify the Department by June 30, 2000 of what corrective actions are going to be taken or have been taken to fix the above deficiencies.

SATISFACTORY

Overall Rating

NONE

Operator w/Inspector

05/01/00

Date: (mm/dd/yy)

*[Signature]*  
DHEC Field Inspector

1225

Military Time

*[Signature]*  
Reviewed By

Inspection was made to determine the operating condition of the plant and, is not to be interpreted that adequate treatment is being provided.

**EXHIBIT #DTW 50**

June 3, 2005


Re: Piney Grove Utilities Log


1. On 5-25-2005 Willie Morgan, Dawn Hipp, Michelle Culbreath, and I went to Lloydwood, Franklin Park, and Albene Park. There were several problems found that need immediate attention.
  - a. One of the problems was a sinkhole in the yard of 315 Lloydwood Dr. The sinkhole has been happening for approx. 1½ years. The homeowner said that Mr. Williams had been out about 1 year ago and couldn't find anything wrong with his system. The homeowner has had numerous tons of white sand hauled in to try to fill the hole, but the sand just keeps caving in. I opened the manhole about 40 yards away and saw white sand in the sewer line trough that comes from the direction of 315 Lloydwood Dr. The manhole is in the yard at 319 Lloydwood Dr. I contacted Mr. Williams on 5-26/05 @ 0830 and informed him of what we had found and told him that it needed to be repaired. I rechecked the problem on 5-27-05 @ 1200 and nothing had been done. I left Mr. Williams a voicemail on 5/27/05 @ 1415 asking him to call me back. Mr. Williams called me back on 5/27/05 @ 1430 and he informed me that the engineer was supposed to be going out to take a look and to come up with a "Plan of Attack." Mr. Williams stated that he would call me back on 5/31/05 and let me know what they were going to do. I have heard nothing up to now, 6/3/05 @ 1045. I have checked and rechecked the sinkhole all this week and nothing has been done up till my last inspection 6/2/05 along with Larry Boland @ 1225.
  - b. Another problem that was found during the 5-25-2005 ride along was in the Franklin Park subdivision. Upon entering Cabin Creek Blvd. It was noted that the rode was caving in on the centerline. It was also noted that there were 2 manholes running down the centerline of the road. We also noticed a dugout area right around where the road is caving in. We spoke with a homeowner and he informed us that a water line going to the other side of the road had been leaking for several months and it took a while to get someone to come and fix the problem. He said that Mr. Williams had someone finally come out and dig up the line, cut it, and cap it off. The repairmen left the hole uncovered and left. It had been noted during a 3-2-05 mCSI that the flow at the wastewater lagoon was over .100mgd while we were there. This tells us that there was water getting into the sewer line somewhere, and somehow. I pulled the manhole that's in the road in front of house number 227 Cabin Creek Blvd. and there appeared to be sand, gravel, and clay in the trough in the manhole that could've been carried down from where the road is caving in. I believe the sewer line has a hole in it around where the road is caving in and somehow the dirt is getting into the sewer line.
  - c. Another continued problem that Mr. Lee Proctor has been working on is 310 Cooksmount. This home has sewage coming up from their cleanout, but there plumber says that when he runs a snake down the line it goes out to under the road before it hits a stopping point. This has been a problem area for several years, but the man has now had the problem without it getting fixed for around 3-4 months that I'm aware of. We can't find the manhole in the area, so we can't figure out the responsibility and I've asked Mr. Williams on several occasions to locate the manholes so they can figure it out.


2. I called Mr. Louis Lang and informed him of these three problems 6/2/05 @ 1515 and he informed me that he would get them to the Mr. Williams.
3. On 6-7-2005 I (Brad Martin) made a visit to the Lloydwood and Franklin Park subdivisions to check on the above issues. I found that the sinkholes in Lloydwood and Franklin Parks were as before with nothing fixed. I also checked the 310 Cooksmount Rd. problem and sewage was still coming up in this individuals yard. I also happened to check a manhole at 304 Carterhill Dr. and found that it was almost full, and this manhole is approx. 4-6 feet deep. I went on down the line and checked the manhole at 314 Carterhill Dr. and it was flowing, but very slowly. I call the 803-606-9224 & the 843-200-4876 numbers on 6-7-2005 @ 1318 and left voicemail messages about this problem and left word for a return phone call on both numbers.
4. I (Brad Martin) visited 421 and 417 Old Plantation Dr. in the Lloydwood S/D 6-8-2005 @ 0850 and found the manhole in front of 421 to be full and almost overflowing. The manhole at 417 was full of some type of unexplainable debris. These visits were made based on a complaint on 6-7-2005 about the manhole in front of 421 overflowing. Keith Collinsworth went out on the evening of 6-7-2005 and didn't see them overflowing, but he could see a small amount of solids around the manhole at 421 that would indicate some form of release. Mrs. Ann Clark called Mr. Williams phone numbers @ 0948 and they called back and stated that they were sending someone right out.
5. I (Brad Martin) visited 421 & 417 Old Plantation Dr. 6-9-2005 @ 1030 and found the lines to still be in the same condition. When I arrived I found that a property owner in the area had called Midlands Utilities and asked them if they could come out there and help them to stop the problems so that their sewage would flow right. Midlands Utilities was trying to jet rod the line, but they were having trouble finding out where the lines ran. I had to leave and try and perform my other duties, so as I was leaving Keith Parnell called his employee and informed him that Mr. Williams had called him and told him that someone was on his way with a set of plans to help. They also informed me that they would be in contact with our office to let us know what they were doing. I arrived back at the office at 1345, and found that Mr. Claude McMillan was waiting and he had a set of plans for us. Mr. McMillan told me that the problems had been taken care of, and they were still waiting on the guy that is supposed to look at the 310 Cooksmount problem and the sinkhole at 315 Lloydwood Dr. Mr. McMillan informed me that the problems in Franklin Park are all because of water problems, not sewer problems, and they were going to snake it when the above mentioned guy has time. Mr. McMillan wanted me to let everyone know that the leaking valve in the tank house in Albene Park has been fixed and that they have a new chemical pump in there as well.
6. I (Brad Martin) visited Lloydwood on 6/13/2005 to make sure the repairs had been finished at 417 & 421 Old Plantation Dr. The manholes were not full anymore, but the trough that the wastewater runs through wasn't flowing. I also went by 310 Cooksmount and the sinkhole on Lloydwood Dr. and nothing has been done to repair these problems.








































































# **WARNING**

By Order of the S.C. Department of  
Health and Environmental Control

**NO:**


**SWIMMING**

**WADING**

**FISHING**

**USING WATER FOR IRRIGATION**

Keep pets and livestock away from water











# *R Lloydwood*

## PLANT DAILY MONTHLY LOG

YEAR 2005*Final Effluent*MONTH 7/11

DATE	TIME	P.H.	D.O.	TEMP.	CHLORINE	CHL.AFT.	DECHL.	ADDED CHEMICALS	FLOW	REMARKS
5/1	16:15	6.39	2.38	11.1°	72.20	0.85			677703	P
5/2	11:53	6.28	3.81	16.2°	72.20	0.5/0.7		Tablets to bucket	677720	
5/3	17:20	6.43	2.91		72.20	0.33/0.8			677730	
5/4	14:15	6.16	2.26	17.2°	72.20	0.25/0.4			7	P
5/5	11:13	6.08	2.41		72.20	0.1/0.7		Tablets in bucket	677750	P
5/6	11:41	6.12	2.81	15.2°	72.20	0.1/0.1		Added tablets	677800	P
5/7	08:40	6.18	3.21	14.2°	72.20	0.5/0.7		No tablets (removed)	677830	P
<i>Broken Source</i>										
5/11	13:45	5.98	2.84		72.20	0.2/0.5			677820	P

























# *R Lloydwood* PLANT DAILY MONTHLY LOG

YEAR 2005

*Final Effluent*

MONTH 7th

DATE	TIME	P.H.	D.O.	TEMP.	CHLORINE	CHL.AFT.	DECHL.	ADDED CHEMICALS	FLOW	REMARKS
5/1	16:15	6.39	2.38	11.12	77.20	0	85		677920	R
5/2	16:28	6.28	3.81	16.22	77.20	0.5	07	Tablet to bucket	677920	
5/3	17:20	6.43	2.91		77.20	0.33	08		6780850	
5/4	14:45	6.16	2.24	17.2	77.20	0.25	04			Ref
5/5	11:13	6.08	2.45		77.20	0.1	07	Water in tank	6781950	
5/6	11:41	6.1	2.81	15.2	77.20	0.1	01	Added table to	6786650	
5/7	08:40	6.18	3.21	14.2	77.20	0.5	07	No table (removed)	6787350	
<div> <p><i>Broken</i></p> <p><i>Source</i></p> </div>										
5/11	13:40	5.98	2.84		77.20	0.2	05		6786200	-2

*Garfield*

**PLANT DAILY MONTHLY LOG**

YEAR 1988

**GARFIELD'S  
ENVIRONMENTAL  
SERVICES**

*Process Control*

MONTH May

DATE	TIME A.M.	D.O.	TEMP.	CHLORINE CHL/AFT	DECHL.	ADDED CHEMICALS	FLOW	REMARKS
5	12:00	21	11.2					RT
5	12:30	21	11.2			Water Supply		RT
5	1:00						N/A	
5	1:30						N/A	
5	2:00	21	11.2					RT
5	2:30	21	11.2					RT
5	3:00	21	11.2					RT
5	3:30	21	11.2					RT
5	4:00	21	11.2					RT
5	4:30	21	11.2					RT
5	5:00	21	11.2					RT
5	5:30	21	11.2					RT
5	6:00	21	11.2					RT
5	6:30	21	11.2					RT
5	7:00	21	11.2					RT
5	7:30	21	11.2					RT
5	8:00	21	11.2					RT
5	8:30	21	11.2					RT
5	9:00	21	11.2					RT
5	9:30	21	11.2					RT
5	10:00	21	11.2					RT
5	10:30	21	11.2					RT
5	11:00	21	11.2					RT
5	11:30	21	11.2					RT
5	12:00	21	11.2					RT
5	12:30	21	11.2					RT
5	1:00	21	11.2					RT
5	1:30	21	11.2					RT
5	2:00	21	11.2					RT
5	2:30	21	11.2					RT
5	3:00	21	11.2					RT
5	3:30	21	11.2					RT
5	4:00	21	11.2					RT
5	4:30	21	11.2					RT
5	5:00	21	11.2					RT
5	5:30	21	11.2					RT
5	6:00	21	11.2					RT
5	6:30	21	11.2					RT
5	7:00	21	11.2					RT
5	7:30	21	11.2					RT
5	8:00	21	11.2					RT
5	8:30	21	11.2					RT
5	9:00	21	11.2					RT
5	9:30	21	11.2					RT
5	10:00	21	11.2					RT
5	10:30	21	11.2					RT
5	11:00	21	11.2					RT
5	11:30	21	11.2					RT
5	12:00	21	11.2					RT
5	12:30	21	11.2					RT
5	1:00	21	11.2					RT
5	1:30	21	11.2					RT
5	2:00	21	11.2					RT
5	2:30	21	11.2					RT
5	3:00	21	11.2					

